



GUARDIAN

FIRE EQUIPMENT, INC.
MIAMI, FL

Ph. 800.327.6584 • Fax 800.827.3869

DETAIL AND SUBMITTAL SHEET

9500 Series - Floor Control and Test Module

Project/Location: _____

Date: _____

Architect/Engineer: _____

Qty: _____

Contractor: _____

Appropriate Selection

Function: Provide zone control for sprinkler line.

Testing: Pressure Regulating Valves can be flow-tested without shutting down sprinkler system (as per NFPA 25).

Installation: Modules are factory-assembled, effectively reducing installation costs and time.

- 2 1/2" Pressure Regulating Valve* with supervisory switch
- Grooved pipe ends
- Water flow detector
- Liquid-filled pressure gauges on inlet/outlet
- 2 1/2" Hose test connection with valve and cap
- Test and drain with pressure relief by-pass

*Choice of factory-set or field-adjustable

| Model No. | Description |
|-------------------------------|--------------------------------|
| <input type="checkbox"/> 9527 | 2 1/2" Straight pattern module |
| <input type="checkbox"/> 9529 | 2 1/2" Angle pattern module |

Select Valve & Flow

Valve Type: **Factory-Set** **Field-Adjustable**
Pressure Regulating Pressure Regulating

Flow Direction: Left to Right Right to Left

Accessories For Testing

- Model 3444** 2 1/2" Double jacket hoses for Flowmeter and Drain Riser connections, refer to 3400 Series. Specify Length _____
- Model 8225** Universal spanner wrench, refer to 8200 Series
- Model 9415** 2 1/2" Flowmeter, refer to 9400 Series

